

COBOD Training L1

Module 1.1

Modelling for 3DCP

Instructor name: Andrei Moraru
P&I – Architectural Technologist

For questions, please contact: amo@cobod.com



INFORMATION DISCLAIMER

This document or embodiment of it in any media and the information contained in it are the property of COBOD International A/S, Copenhagen, Denmark.

It is an unpublished work protected under copyright laws free of any legal responsibility for errors or omissions.

It is supplied in confidence, and it must not be used without the express written consent of COBOD International A/S for any other purpose than for which is supplied.


It must not be reproduced in whole or in part in any way (including reproduction as a derivation work) nor loaned to any third party.

This document must be returned to COBOD International A/S on demand.



TIMELINE

3D PRINTING CONSTRUCTION



AGENDA AND OBJECTIVES


1. INTRODUCTION AND INDEX (5 MIN)
2. DOCUMENTS THAT SUPPORT THIS MODULE (5 MIN)
3. SYSTEM OVERVIEW (5 MIN)
4. MODELING IN THE OVERALL 3DCP PROCESS DIAGRAM (5 MIN)
5. CONSTRUCTION PHASES IN 3DCP (5 MIN)
6. KEY PERFORMANCE INDICATORS (5 MIN)
7. 3DCP LOGISTICS (20 MIN)
8. MODELING CONSIDERATIONS (30 MIN)
9. STRUCTURAL DESIGN CONSIDERATIONS (30 MIN)
10. RECAP (10 MIN)
11. QUIZ AND QUESTIONS (30 MIN)

COBOD CONFIGURATOR



www.cobod.com/configurator/

COBOD CONNECT – LIBRARY AND RESOURCES



The screenshot shows the COBOD Connect website interface. At the top, there is a navigation bar with the COBOD logo on the left and menu items: ACADEMY, FORUM, KNOWLEDGE BASE, DOWNLOADS, SHOP, and TECH SUPPORT. On the right side of the navigation bar, there are icons for a user profile, a shopping cart with '(0)', and a download icon with '(0)'. The main header features a large image of a building facade with the COBOD logo in the background. The text 'COBOD CONNECT' is prominently displayed in white, with the subtitle 'A COBOD customer service platform' below it. Below the header is a 'NEWS' section with four news items, each with a thumbnail image and a title:

- BAKRIE AND COBOD ESTABLISH JOINT VENTURE FOR 3D CONSTRUCTION PRINTING IN INDONESIA**
COBOD International A/S has established a JV agreement with PT Modula Sustainability Indonesia, a subsidiary of PT Bakrie & Brothers Tbk (BNBR) specializing in 3-dimensional
- ORASCOM CONSTRUCTION AND COBOD CREATE JV**
Orascom Construction PLC (NASDAQ Dubai: OC; EGX: ORAS) announces that it has formed an exclusive partnership with Denmark-based COBOD International to bring the latest 3D Printing Construction ("3DPC") technology for the
- HOLCIM INVESTS IN COBOD**
Holcim announces its investment in COBOD International, a global leader in 3D construction printing, to advance world-class 3D printing materials, robotics, and automation together.
- CEMEX**
This inve deliver a by digita



WARRANTY DISCLAIMER


It is important to read and understand the following concepts about your product warranty:

- Warranty covers 14 months from the date the shipment departs COBOD's production facilities.
- Warranty covers free replacement of defective or missing mechanical and electrical parts.
- Warranty covers online remote support to install the parts and shipping of the parts.
- Warranty does not cover consumables or wearable parts.
- Alterations or external additions made to the equipment that are not approved by COBOD R&D technical board prior to being implemented will void warranty. Such changes include (but are not limited to):
 - Printer system changes.
 - Changes to the material delivery system or hose management.
 - Removal or covering of COBOD logos, branding stickers and other trademarks on the equipment.
 - Tampering, removal or changes to original safety elements, classification stickers or signs on the equipment.
- Failure to maintain the equipment according to the maintenance guidelines will void warranty.
- Failure to operate the equipment according to the operational guidelines will void warranty.
- In addition to the loss of warranty, modifying equipment against the manufacturer's advice is not recommended as this could generate serious safety hazards for users.
- Operation with materials not suitable for use with the COBOD -equipment will void warranty. Ask COBOD if there is any doubt about the suitability of the materials.
- The responsibility to provide sufficient documentation in the form of incident reports and/or maintenance evidence lies with the owner of the equipment.

COBOD's technical team will assess each case to determine if warranty is applicable based on the information provided above.

DOCUMENTATION THAT SUPPORT THIS MODULE

1. STANDARD OPERATIONAL PROCEDURE – MODELLING AND SLICING
2. STANDARD OPERATIONAL PROCEDURE – BOD2
3. WC1 – CONSTRUCTION DETAILS
4. DESIGN EXAMPLES




SYSTEM OVERVIEW

BOD 2 - 3D PRINTER

Hose Management System (HMS)

Printer System


Material Delivery System (MDS)



SYSTEM FOCUS

BOD 2 - 3D PRINTER

Printer System




Printable area (PA)

MODELING IN THE OVERALL 3DCP PROCESS DIAGRAM

WEEK PROGRESS



**Converting a 3D/
BIM model into a
3D printable file.**



**Slicing the
geometry and
DIGITAL RUN.**



**BOD2 Installation,
Operation and
DRY RUN.**



3DCP Materials.



**Material Delivery
System
and HMS.**


LAYER AS THE 3DCP UNIT

LAYER PARTS


LAYER SPECIFICATIONS

Layer specifications such as centerlines, height and width (that create high or low resolution, high or low production) can vary depending on the design criteria, however, it is important to decide such parameters when you start designing a 3DCP building as they will significantly impact look, operation and quality control of your product.


Basic dimensions



End and start parameters




Resolution



CORNERS

A 3D printer cannot make 90 degrees sharp corners, which is why when you are modeling, the corners must have a fillet.

The radius of the fillet must be greater or equal to your layer width. For example, if you have a wall which is 50mm, then the radius of your corner fillet must be equal or greater than 50mm, or as a reference, the radius of the corners is equal to the width of your nozzle.



▶ CHOOSING THE RIGHT NOZZLE

MODELING CONSIDERATIONS SECTION

A nozzle is the mechanical end part of the 3d printer where material comes out and it is directly related with your wall design.

It is important to understand the different types of nozzles that exist, and the role nozzles play in design, quality control and operation to ensure a smooth printing experience.

Your 3D printer comes with steel nozzles varying in size. For mortar printheads the default dimensions are 50x20 mm (width x length) and for HT (high throughput) printheads the dimensions are 50x40 mm and 80x30 mm (width x length).

Flaps can be attached to the nozzle on either one or both sides. The flaps help to ensure achieving the intended layer width and gives a better surface quality overall. See picture of nozzle without (left) and with flaps (right) to the right.



Generally speaking, you should know:

- Type of nozzle (round or square).
- Material of your nozzle (stainless steel or plastic).
- Dimensions, connections, front and back sides.
- If you will be using 2 flaps, 1 flap or none.

FLAP USE

LAYER SPECIFICATIONS

Using or not using flaps has direct implications in your project and printing extrusion control.

Implications are related to inventory, health and esthetic look.


When flaps are not used a rounder layer edge is formed and creates pockets that might collect dust or mold overtime as well as pockets for insects while consuming more material in the process. A higher extrusion control will also be needed from your printer operator.

Using flaps will maintain the shape better while consuming less material providing a more uniform look.

Different sizes of flaps are included in your product to address different scenarios, inserting the dimensions of the flap you choose will be an important step during the slicing process.

You can choose to use a flap in both sides (internal and external) or only external. Not paying attention to the internal flap during printer travels might result in accidental wall cut during operations.

Nozzle without flaps



Round edges

Nozzle with flaps



Flat edges

CENTERLINES

LAYER SPECIFICATIONS

A centerline is a theoretical surface or plane representing the center of each 3D printed element. This surface is then imported into COBOD Slicer where it will be divided into individual horizontal layers, which will act as toolpaths for the 3D printer to deposit material layer by layer.


A centerline runs exactly through the middle of the nozzle as seen in the pictures.

The start and end point of a centerline is defined exactly in the middle of the circle from the top of the nozzle.


Nozzle without flaps




Centerline in nozzle




Centerline in reference to edges




Front view



Top view



Centerline in COBOD Slice



LAYER TIME

LAYER SPECIFICATIONS



Good layer bonding, but **too much slump resulting in sunken layers**, and the need to compensate with more extrusion

TOO FAST 



Steady layer width and even layers, but **very poor layer adhesion resulting in poor strength and durability**

TOO SLOW 




Steady layer width and good layer bonding

OPTIMAL 

LAYER TIME EXAMPLES

LAYER SPECIFICATIONS

	Case 1	Case 2	Case 3
Print speed	300 mm/sec	100 mm/sec	85 mm/sec
Layer time	2 min 60s	5 min	8 min 40s
Conclusion	Too fast ✗	Too fast ✗	Optimal ✓



The following factors will affect your layer time:

- ❖ Weather conditions
- ❖ Material performance
- ❖ Geometry size
- ❖ Desired resolution
- ❖ Geometry complexity
- ❖ Printer operator performance

KEY PERFORMANCE INDICATORS (KPIs) FOR MODELING

KEY PERFORMANCE INDICATORS

1 3DCP LOGISTICS

Definition: 3DCP logistics is the optimization of your printable units, site planning and printing time in accordance with the volume output of material per hour.

Measurement unit: X m3 of material/h

- | | |
|--|--|
| <ul style="list-style-type: none"> - Project management - Site plan optimization - Utilities needed - Tools needed - Trained crew | <ul style="list-style-type: none"> - Poor planning - No site plan - Tools missing - Crew is not trained, no clarity in roles |
|--|--|



2 MODELING CONSIDERATIONS

Definition: The modeling considerations are the key elements which will make your design 3D printable, including printable area, wall design, and openings.

Measurement unit: YES/NO

- | | |
|---|---|
| <ul style="list-style-type: none"> - Less junctions - No thermal bridges - Defining details - Openings considerations according to layer height - Flaps/no flaps | <ul style="list-style-type: none"> - Many junctions - Many small pieces - Not understanding your nozzle - Radius for corners is less than the width of the nozzle |
|---|---|



3 STRUCTURAL CONSIDERATIONS

Definition: Structural considerations are the key elements which will be approved by your structural engineer in order to obtain the building permit. These will include foundation, column and slabs.

Measurement unit: YES/NO

- | | |
|--|--|
| <ul style="list-style-type: none"> - Regulation compliance - Structural details - Structural drawings approved - Overlap reinforcement for columns | <ul style="list-style-type: none"> - Structural elements are not well planned and ready. - Foundation slab is equal to the footprint of the building - Printer is not aligned with foundation |
|--|--|




1

3DCP LOGISTICS

3DCP CONSTRUCTION PHASES

3DCP LOGISTICS SECTION




SITE OPTIMIZATION

3DCP LOGISTICS SECTION

One of the most important factors in 3DCP logistics is the Site optimization.

You want to set-up your site in the best way possible to prevent issues that might occur, or (in case your building is bigger than the printable area and your build is projected to be printed in segments) you must consider printer movements when you plan the arrangement of the equipment on site.

In the image you can see an example on how to arrange the equipment on site to avoid accidents and to have clear visibility from the control station of what is happening when a building is being printed.





2

MODELING CONSIDERATIONS

CONTINUOUS LOOPS

MODELING CONSIDERATIONS SECTION

Continuous loops allows you to 3D print faster, more stable structurally and to get a better surface quality as you will not have too often the seams of start/end of a layer.



AREAS OF YOUR PRINTER

MODELING CONSIDERATIONS



1. Installation area:

The minimum three-dimensional volumetric space required by the printer.

Its maximum outer dimensions.



2. Printing area:

The maximum printing area. This area is the same as operational area, excluding space for cleaning and maintenance operations.



3. Cleaning area:


An area reserved for cleaning and maintenance. This area is needed to allow the X-axis to move down to ground level.

Can be anywhere inside the print area. By aligning openings (doors, windows etc.) it is possible to have the cleaning area anywhere inside the operational area.



4. Operational area:

The maximum three-dimensional space of which the printer can move.




WALL TYPES

MODELING CONSIDERATIONS


3D printing offers almost unlimited opportunities for how you can model the walls. In this section, five different types of walls are illustrated. Further details about this walls can be found in the Design manual document.

These walls can be combined or altered as desired.


There are various advantages and disadvantages for each wall type, and the choice will depend on the overall design and local building regulations.




Hollow wall with integrated column




"Snake wall"



Double wall or "Sandwich wall"




Bespoke double wall



Single wall

Factors to take into consideration when modeling the 3D printed walls:

1. Wall type (loadbearing / non-loadbearing)
2. Wall thickness
3. Insulation layer according to building regulations
4. Avoid thermal bridges if necessary, depending on the building regulations
5. Layer height
6. Layer width



Layer height and width of the 3D printed layer can vary depending on the design criterias.

The most common dimensions are layer height = 20 mm and layer width = 50 mm.

OPENINGS

MODELING CONSIDERATIONS



Voids for both windows and doors should be subtracted from the modelled surfaces. Underlying walls should be created also as a part of the surfaces to support the 3D printed walls around the window.

After the walls around the window are printed, there are several ways to install the lintel. This applies for both windows, doors or other openings.

If a floor to ceiling window is desired, there will naturally be no need for underlying support in the form of 3D printed walls. Therefore, the void can be created in similarity with a door opening. In this way, your building will be printed faster.

Factors to be defined in the design phase before implementing any type of door/window into your project are:

1. Wall thickness and type
2. Avoiding thermal bridges or not
3. Window span and height
4. Window support type: steel plate or 3D printed supports
5. Frame location: towards interior or exterior
6. Window side supports
7. Lintel design




MODELING CONSIDERATIONS

9. OPENINGS (WINDOWS/DOORS)

Window / door detail for avoiding a cold bridge.

At every external wall opening, the printed layers are ending with a U-shaped edge towards the cavity wall. A minimum gap of 5-10cm is required between the two edges to prevent a thermal bridge.



Window Detail from Hostelbro Project – 3D printed House

MODELING CONSIDERATIONS


10. OPENINGS (MEP)

- The necessary voids for the electrical sockets can be included and planned in the CAD file. This will automatically eliminate the need to drill or cut holes in the 3D printed walls, allowing various installations.
- The necessary voids can be cut after the wall is finished; however, we do not recommend this, as it will require heavy machinery and the walls are more prone to crack.
- The necessary voids can be cut right after the print while the material is still wet. This way you can create a clean void for MEP.


The wires can be placed on the inside both external and internal walls if it is designed as double wall.

The main plumbing work will be done while working with the foundation. A complete water piping network must be placed before casting the foundation, leaving pipes sticking out in the cavity wall, similar case to wiring.


Voids for water outlets, cleanout valves can be included in the planned CAD file, or manually removing wet material. Other options are also possible as in having the wiring and plumbing under the roof/slab and covered by the false ceiling.



1
The main water line is placed in the foundation before casting.



2
A void for plumbing is designed in the CAD file for easier installation.



3
The bifurcated pipes from the primary lines are placed in between the walls.

3

STRUCTURAL CONSIDERATIONS

STRUCTURAL CONSIDERATIONS


1. FOUNDATION

We highly recommend using the 3D printer to print the outline border of at least the top part of the foundation, both for orthogonal and more complex shapes. **3D printing the outline of the foundation will make printing the vertical structures a lot easier.** It will also eliminate the need for creating complex formwork to cast the foundation. Then simply pour conventional concrete after 2 days to finish your foundation.

In case manual work is chosen for the foundation, we recommend to build the foundation at least 5-10cm bigger on all sides than the printed geometry. This will avoid any misalignment between the foundation slab and the printable file.

For the top part of the foundation, waterproofing and insulation (if required by the local building code) should be implemented before casting the slab. The figure shows the plumbing pipe sticking out of the base foundation and the 3D printed top part.

As seen in the figure besides, the 3D printer can be installed on concrete feet. This will increase the printable height area. The use of concrete feet will typically add 60cm of printing height.



3D printing a plinth beam foundation directly on the leveled ground.

Base foundation size limited to just fit the shape of the building with 5-10cm tolerance. The top part of the foundation is printed by the 3D printer.

STRUCTURAL CONSIDERATIONS

1. FOUNDATION

REVISIONS:

A	18.April.23	Changes to reinforcement
-	-	-
-	-	-
-	-	-
-	-	-

DESCRIPTION
Casted foundation connection with 3D printed concrete double wall.

Use cases:

- 1,2,3 story house
- Warehouse

ASSEMBLY

- Earth excavation and leveling the soil
- Place gravel under the slab
- Place hard insulation
- Place DPM
- Place the reinforcement for the plinth and slab
- Cast the foundation and slab
- Make the sloped edge 30 min after pouring the concrete
- Place DMP tarp as shown in the drawing) brown line)
- After 1-2 days of curing, the 3D printed walls process can start

COMPANY
COBOD INTERNATIONAL A/S

ADDRESS
Skudehavnsvej 17A
2150 Nordhavn
Denmark +45 9290 9066
info@cobod.com

DRAWN BY:
Andrei Moraru
Architectural Technologist

SCALE:
1:5 (millimeters)

DATE:
14.April.2022

DRAWING NO.:
WC1_F01_C.D01

REVISED BY
ZM

PLINTH FOUNDATION CONNECTION

REVISIONS:

A	18.April.23	Changes to reinforcement
-	-	-
-	-	-
-	-	-
-	-	-

DESCRIPTION
Casted foundation connection with 3D printed concrete double wall.

Use cases:

- 1,2,3 story house
- Warehouse

ASSEMBLY

- Earth excavation and leveling the soil
- Place gravel under the slab
- Place hard insulation
- Place DPM
- Place the reinforcement for the plinth and slab
- Leave Rebar sticking out of the foundation 60cm
- Cast the foundation and slab
- Make the sloped edge 30 min after pouring the concrete
- Place DMP tarp as shown in the drawing) brown line)
- After 1-2 days of curing, the 3D printed

COMPANY
COBOD INTERNATIONAL A/S

ADDRESS
Skudehavnsvej 17A
2150 Nordhavn
Denmark +45 9290 9066
info@cobod.com

DRAWN BY:
Andrei Moraru
Architectural Technologist

SCALE:
1:5 (millimeters)

DATE:
14.April.2022

DRAWING NO.:
WC01_B01_C1_D01

REVISED BY
ZM


PLINTH FOUNDATION CONNECTION WITH COLUMN

STRUCTURAL CONSIDERATIONS


2. COLUMNS

3D printing offers a lot of opportunities and free modeling on how you can print the columns formwork.


Basically, the 3D printer is creating the outer shell of the column, in which you add after the rebar, the cage and fill with normal concrete.



450mm wall with column integrated in the cavity.




400mm wall with column integrated in the cavity.




300mm wall with column integrated in the cavity.

STRUCTURAL CONSIDERATIONS


2. COLUMNS



400mm wall with column integrated in the cavity.




300mm wall with column on the inside.



300mm wall with column integrated in the corner

STRUCTURAL CONSIDERATIONS

2. COLUMNS




Insulate the wall.

Cast with conventional concrete.


Insert reinforcement cage.

3D printing the formwork for the column and the walls.




STRUCTURAL CONSIDERATIONS


2. COLUMNS – FROM FOUNDATION TO THE SLAB/ROOF




3D print formwork for foundation




Add reinforcement




Cast the foundation




3D print the walls and column's formwork



Insert the reinforcement cage




Insulate the wall




Insulate the outer shell

STRUCTURAL CONSIDERATIONS

2. COLUMNS



- Add support formwork for casting the slab
- Add reinforcement



- Cast the slab together with the columns

STRUCTURAL CONSIDERATIONS

3. REINFORCEMENT CONNECTION

Reinforcement can be connected to the foundation by leaving rebar sticking out of the foundation.


Then the printer can deposit the layers around the rebar, creating the necessary formwork for the column.

Next step is to insert the reinforcement cage from the top and overlap it with the rebar connected to the foundation

The overlap is approximately 20 x diameter of the vertical rebar. For example, in these details, the vertical rebar's diameter is 3cm x 20 = 60cm

It is recommended use this technique of connecting reinforcement in the columns, however you have to consider the inner side of 3D printed formwork which will not be perfect if you don't have a flap, ending up to be a formwork thicker than the one in the drawing.

Therefore, is recommended to make the interior of the columns 3-5cm bigger, for inserting smoother the reinforcement cage.




STRUCTURAL CONSIDERATIONS


3. REINFORCEMENT CONNECTION



3D print around column rebar up risers using extension nozzle. Leaving a small opening for rebar connecting.



Insert column rebar from top of the wall, use rebar coupler to connect column rebar with rebar up risers.



Use temporary formwork for the opening and cast concrete in column.

STRUCTURAL CONSIDERATION

4. SLAB CONNECTION

There are different types of slabs that can be used in 3DCP, these types of slabs can be used in floors as well as in roof structures.

1. Cast in situ RCC.
2. Precast slabs (hollow core, double T, etc).
3. Filigree slabs (recommended when the shape of the building is complex. These slabs can be 3D printed).
4. Steel or wooden decks.

REVISIONS:

A	18.April.23	Changes to reinforcement
-	-	-
-	-	-
-	-	-
-	-	-

DESCRIPTION
Casted foundation connection with 3D printed concrete double wall.

Use cases:

- 1,2,3 story house
- Warehouse

ASSEMBLY

- 3D print the inner leaf and the column's formwork until the bottom of the slab
- 3D print the outer leaf until the top of the deck, to act as formwork for casting
- Place hard insulation to avoid a thermal bridge on the side.
- Add reinforcement to connect the column to the slab and cast the rest.
- Continue 3D printing the parapet
- Finish the roof conventionally

COMPANY
COBOD INTERNATIONAL A/S

ADDRESS
Skudehavnsvej 17A
2150 Nordhavn
Denmark +45 9290 9066
info@cobod.com

DRAWN BY:
Andrei Moraru
Architectural Technologist

SCALE:
1:5 (millimeters)

DATE:
14.April.2022

DRAWING NO.:
WC01_B02_C1_D02

REVISED BY:
ZM

REVISIONS:

A	18.April.23	Changes to reinforcement
-	-	-
-	-	-
-	-	-
-	-	-

DESCRIPTION
Casted foundation connection with 3D printed concrete double wall.

Use cases:

- 1,2,3 story house
- Warehouse

ASSEMBLY

- Add frequent wall ties on the layer at the bottom of the beam
- 3D print the inner leaf until the bottom of the slab
- 3D print the outer leaf until the top of the deck, to act as formwork for casting
- Place hard insulation to avoid a thermal bridge on the side.
- Place hard insulation or steel mesh to act as horizontal formwork for the beam
- Add reinforcement for the beam and the slab and cast with conventional concrete
- Continue 3D printing the parapet
- Finish the roof conventionally

COMPANY
COBOD INTERNATIONAL A/S

ADDRESS
Skudehavnsvej 17A
2150 Nordhavn
Denmark +45 9290 9066
info@cobod.com

DRAWN BY:
Andrei Moraru
Architectural Technologist

SCALE:
1:5 (millimeters)

DATE:
14.April.2022

DRAWING NO.:
WC01_B02_C0_D02

REVISED BY:
ZM

STRUCTURAL CONSIDERATIONS

4. SLAB CONNECTION

Cast in situ slabs, or prefabricated elements can be connected to 3D printed walls similarly with conventional techniques.

For cast in situ beams, a permanent formwork is placed on top of the 3D printed layers with 1/2 overlap, then the printer can continue to 3D print the walls.

Insert the reinforcement cage with spacers and cast it.

Create the formwork for the casted slab or in case of prefabricated hollowcore slabs, just rest them on the beams, then continue with the second floor.

REVISIONS:

A	18.April.23	Changes to reinforcement
-	-	-
-	-	-
-	-	-
-	-	-

DESCRIPTION

Casted foundation connection with 3D printed concrete double wall.

Use cases:

- 1,2,3 story house
- Warehouse

ASSEMBLY

- 3D print the inner leaf and the column's formwork until the bottom of the slab
- 3D print the outer leaf until the top of the deck, to act as formwork for casting
- Place hard insulation to avoid a thermal bridge on the side.
- Add reinforcement to connect the column to the slab and cast the rest
- Continue 3D printing the parapet
- Finish the roof conventionally

PARAPET ROOF CONNECTION WITH HOLLOW-CORE DECK AND COLUMN

COMPANY COBOD INTERNATIONAL A/S	ADDRESS Skudehavnsvej 17A 2150 Nordhavn Denmark +45 9290 9066 info@cobod.com	DRAWN BY: Andrei Moraru Architectural Technologist	SCALE: 1:5 (millimeters)	DRAWING NO.: WC01_B02_C1_D01
			DATE: 14.April.2022	REVISED BY ZM

STRUCTURAL CONSIDERATIONS

5. ROOF CONNECTION

Roofs and slabs are very much similar with conventional construction, they follow the same principles of connecting the rebars from foundation to the roof.

Continue 3D printing the parapet and apply the roof finishes.

This is an example of 3D printed slab called filigree concrete slab with 3D printed formwork.

EXTERIOR

INTERIOR

REVISIONS:

A	18.April.23	Changes to reinforcement
-		
-		
-		
-		

DESCRIPTION

Casted foundation connection with 3D printed concrete double wall.

Use cases:

- 1,2,3 story house
- Warehouse

ASSEMBLY

- 3D print the inner leaf and the column's formwork until the bottom of the slab
- 3D print the outer leaf until the top of the deck, to act as formwork for casting
- Place hard insulation to avoid a thermal bridge on the side.
- Add the Filigree slab and connect it to the column
- Cast the rest of the filigree slab
- Continue 3D printing the parapet
- Finish the roof conventionally

PARAPET ROOF CONNECTION WITH FILIGREE DECK AND COLUMN

COMPANY
COBOD INTERNATIONAL A/S

ADDRESS
Skudehavnsvej 17A
2150 Nordhavn
Denmark +45 9290 9066
info@cobod.com

DRAWN BY:
Andrei Moraru
Architectural Technologist

SCALE:
1:5 (millimeters)

DATE:
14.April.2022

DRAWING NO.:
WC01_B02_C1_D07

REVISED BY:
ZM

SPECIAL CONSIDERATIONS

SPECIAL CONSIDERATIONS

1. PRINTING A GEOMETRY BIGGER THAN THE PRINTABLE AREA.




If your design is bigger than the printable area, you might consider splitting the building in 2-3 parts and print them individually.

In this case, you need to consider these movements of the printer when you are designing your building.

For this project, it was decided to have floor to ceiling windows in order to join perfectly the 3 3D printed sections.

There is a lot of design freedom on how to cover those gaps: floor to ceiling windows, cast concrete, 3D print that section as a piece of wall and insert it in the gap, etc.

However, we recommend to design according to your printable area, and if you need to move the printer, design and model accordingly.



SPECIAL CONSIDERATIONS

2. 3D PRINTED FILIGREE ROOF SLAB



3D Print Formwork



Place Reinforcement



Cast the First 6-8cm



Place Roof Slabs on the Building



Cast the Last 12-14cm on Site



CAD VS SLICER

INPUTS NEEDED FOR A GEOMETRY

Some inputs are exclusively done in the CAD software, and some are exclusively done in the COBOD Slice, it is important to understand what needs to be done in each so you can correct properly.

	CAD	COBOD Slice
Walls	X	
Centerlines	X	
Layer Height		X
Location in space (XYZ)	X	
Layer Width		X
Print speed		X
Openings	X	
Solids	X	
Joining Centerlines	X	
Seams	X	X
Order of objects		X
Any other cuts in the walls (MEP)	X	
G-code		X


REVIT PLUG-IN

FAQ

1. How to download and install the Revit Plug-in?

Go on connect.cobod.com/software/revit-plugin and download the files + the manual on how to install and use it.

2. Can you export a step file from Revit? – YES
3. Can I use my own Revit Template? – No, use the provided template form COBOD Connect.
4. What type of objects can this Plug-in handle? - All geometries except walls created with spline, sloped surfaces or parametric design.



RECAP KPI

1 3DCP LOGISTICS

Definition: 3DCP logistics is the optimization of your printable units, site planning and printing time in accordance with the volume output of material per hour.

Measurement unit: X m3 of material/h

- | | |
|--|--|
| <ul style="list-style-type: none"> - Project management - Site plan optimization - Utilities needed - Tools needed - Trained crew | <ul style="list-style-type: none"> - Poor planning - No site plan - Tools missing - Crew is not trained, no clarity in roles |
|--|--|



2 MODELING CONSIDERATIONS

Definition: The modeling considerations are the key elements which will make your design 3D printable, including printable area, wall design, and openings.

Measurement unit: YES/NO

- | | |
|---|---|
| <ul style="list-style-type: none"> - Less junctions - No thermal bridges - Defining details - Openings considerations according to layer height - Flaps/no flaps | <ul style="list-style-type: none"> - Many junctions - Many small pieces - Not understanding your nozzle - Radius for corners is less than the width of the nozzle |
|---|---|



3 STRUCTURAL CONSIDERATIONS

Definition: Structural considerations are the key elements which will be approved by your structural engineer in order to obtain the building permit. These will include foundation, column and slabs.

Measurement unit: YES/NO

- | | |
|--|--|
| <ul style="list-style-type: none"> - Regulation compliance - Structural details - Structural drawings approved - Overlap reinforcement for columns | <ul style="list-style-type: none"> - Structural elements are not well planned and ready. - Foundation slab is equal to the footprint of the building - Printer is not aligned with foundation |
|--|--|



MOST COMMON MODELING MISTAKES FOR BEGINNERS

Centerlines are not joined

The centerlines of closed loops must be joined in order to select the geometry in the Slicer as one object.

If the centerlines are not joined, the slicer will see them as separate objects.

Centerlines are joined

The centerlines of unclosed loops must not be joined in order to select the geometry in the Slicer as one object.

If the centerlines are joined, the slicer will not see them as separate objects.

Solids are not modeled

Solids must be modeled in the STEP file in order to be avoided by the Printhead. After you modelled them, make sure in the Slicer you add them as external objects.

Model is not at Z0

Every geometry you want to be 3D printed, needs to be set at Z0, including the foundation formwork.

Keep the foundation under Z0 in your drawings, but not in the model for printing.

Radius of corners is too small

Creating a fillet for corners with a smaller radius than the width of the nozzle will create an imperfect corner after is 3D printed.


Make sure to create the fillet equal or grater than the width of the nozzle used for 3D printing.

Foundation Does not have 5-10cm offset

If you cast the slab before, the foundation should have an offset of 5-10 cm on each side, after which the walls can be modelled on top.

This will prevent any misalignment between the walls, foundation and the printer.

Make sure you understand which centerlines need to be joined and which not.



CERTIFICATION TEST

TEST CRITERIA

- ▶ Link: <https://www.flexiquiz.com/SC/N/eb7561f7-91c2-42cd-aa02-41f444f3e277>
- ▶ Time limit: 20 minutes.
- ▶ Dynamic: All documents can be used as help.
- ▶ Approval: At least an 80% score to pass.
- ▶ Sequenced: Need to pass Level 1 test before proceeding to site training (Level 2).

**THANK YOU FOR
YOUR ATTENTION!**

